



Integrating Additive Manufacturing with Accelerated Bridge Construction Techniques

Amir H. Alavi, PhD
IRISE Annual Meeting
May 23rd, 2024




The Research Problem

Modular forms of bridge construction have been of continued interest in prefabricated bridge elements and systems (**PBES**)

The Limitations:

- High cost for developing modular forms
- Time consuming and labor intensive
- Construction safety concerns
- Limited customizability

The Needs:



Increase the construction quality of PBES



Reduce their construction time and labor cost



Enhance the safety and reliability



Minimize the environmental footprint of the PBES fabrication plants



Produce structural elements with optimized topologies



Enable in-situ repair of existing ABC elements via customizable design

Project Objectives/Deliverables


Objectives:

- Explore the feasibility of integrating additive manufacturing with ABC techniques in Pennsylvania
- Identifying, fabricating and mechanical testing of 3D printable prefabricated bridge elements currently used in ABC projects



Tasks and Deliverables:

- Task A: Review of the stat-of-the-art of 3D concrete printing research
- Task B: Identifying optimal 3DCP reinforcement
- Task C: 3D printing of prefabricated elements in ABC systems
- Task D: Development of recommendations
- Task E: Final report



Literature Review


Potential Reinforcement Strategies:



Placing steel reinforcement horizontally between 3d-printed concrete layers




Concrete floor slabs with add-on-printed reinforced ribs



Placing vertical reinforcement in 3D printed formwork



Post-tensioning of steel reinforcement placed in 3D printed conduits




Mesh insertion and embedment using the custom-designed 3D printing nozzle


Concrete Beam 3D Printing

Without Reinforcement

Printed Formwork



Printed Entire Sample




With Reinforcement

Printed Formwork with Reinforcement




Printed Entire Sample with Reinforcement



Concrete Beam 3D Printing


Without Reinforcement

Printed Studs Formwork



With Reinforcement

Printed Studs Formwork with Reinforcement



Sikacrete^R -752 3D micro-concrete

Compressive strength ¹	1 st day	~2,900 psi
	7 th day	~5800 psi
	28 th day	~7,250 psi
Flexural strength ²	~1,000 psi	
Water penetration under pressure ³	~0.8 inch	
Service temperature	Under 212 °F	

1) Tested at +77 °F, w/c=17% (1.10-gallon water per 55 lb bag) (ASTM C109)

2) Tested at +77 °F, w/c=17% (1.10-gallon water per 55 lb bag) (ASTM C348)


3) Tested at +77 °F, w/c=17% (1.10-gallon water per 55 lb bag)

Printed Entire Sample with Staples



Concrete Beam Tests


Cast



Printed Entire Sample




Printed Formwork




Concrete Beam Tests


Cast with Reinforcement



Printed Formwork with Reinforcement



Concrete Beam Test Results



Concrete Beam Test Results

Casted-Plain

Beam Width	6	in
Beam Height	6	in
Max Load	5.17	kips
Max Stress	646.33	psi



3DP-Walls-Plain

Beam Width	8	in
Beam Height	6	in
Max Load	4.20	kips
Max Stress	393.45	psi



3DP-Stud-Plain

Beam Width	8	in
Beam Height	7	in
Max Load	4.82	kips
Max Stress	331.69	psi



Fully Printed-Plain

Beam Width	8	in
Beam Height	6	in
Max Load	8.26	kips
Max Stress	774.31	psi



Casted-Rebar

Beam Width	6	in
Beam Height	6	in
Max Load	13.64	kips
Max Stress	1704.90	psi



3DP Wall-Rebar

Beam Width	9.5	in
Beam Height	6	in
Max Load	19.63	kips
Max Stress	1549.43	psi



3DP-Stud-Rebar

Beam Width	7	in
Beam Height	7	in
Max Load	29.46	kips
Max Stress	2319.04	psi



Fully Printed-Rebar

Beam Width	10	in
Beam Height	7	in
Max Load	34.06	kips
Max Stress	1876.64	psi



Fully Printed-Staple


Beam Width	8	in
Beam Height	6	in
Max Load	5.07	kips
Max Stress	474.94	psi



Bridge Component Selection

Main Components:


- Abutment
- Girder
- Bent Beam
- Piers



**Final Decision:
Pier cap**



Pier Cap Design Details



Micro-concrete

Compressive Strength	1 day	7 days	28 days
	~2900 psi	~5800 psi	~7250 psi
Flexural Strength	~1000 psi (28 days, 77 °F, 17% w/c ratio)		

Standard Concrete

Compressive Strength	28 days
	4000-10000 psi
Flexural Strength	800~1200 psi



Pier Cap Design and 3D Printing


Conventionally Cast Reinforced Pier Cap



3DCP of Pier Cap Formwork




Pier Cap Test Results



Shear Failure of Pier Caps


Conventionally Cast



3DCP







Stress-strain curves




Pier Cap Test Results

Numerical Simulations



Summary

- **Feasibility of using additive manufacturing for developing PBES for ABC**
- **3DCP beams without refinement demonstrated acceptable strength results compared to the conventionally cast samples**
- **Reinforced 3D printing formwork with studs showed higher strength than other samples**
- **Conventionally cast pier cap provided a similar strength to the cap with reinforced 3DCP formwork with studs**
- **The 3D printed pier cap exhibited higher stiffness**



Further Considerations

- Exploring the stapling reinforcement method (e.g. understanding how overlaps influence strength)
- Investigating the integration of smart technologies, such as sensors and monitoring systems, into 3DCP prefabricated elements
- Material discrepancies: The divergence in materials between 3DCP and traditional concrete introduces a challenge
- Durability and long-term performance



Acknowledgement

Project Panel

Jason Zang, PennDOT
Nick Shrawder, PennDOT
Jonathan Buck, FHWA
John Boyer, Pennsylvania Turnpike
Richard Connors, Allegheny County
&
Shelley Scott, PennDOT

Graduate students

Wendy Lu
Gloria Zhang
Aron Griffin
Kaveh Barri
Hao Yu

Undergraduate students

Callum Grealy
Ariel Holstein
Quinn Aker
Bailey McCausland



Thank you

Impactful Resilient Infrastructure Science and Engineering (IRISE)
<https://www.engineering.pitt.edu/subsites/consortiums/irise/>



**Intelligent Structures and Architected Materials
Research and Testing (ISmart) Laboratory**

<https://pitt.edu/~alavi/>



University of
Pittsburgh

Swanson School
of Engineering

ENGINEERING EXCELLENCE SINCE 1846

PITT | **IRISE**